



दक्षिण मध्य रेलवे  
SOUTH CENTRAL RAILWAY  
प्रमुख मुख्य इन्जिनर कर््यालय/ PCE's Office  
कार्य शाखा/ क / Works Branch  
रेल निलयम / Rail Nilayam  
सिकंदराबाद / Secunderabad

Ph.No. 040-27822004  
Rly: 070- 86365  
email: dyceworks@scr@gmail.com

दिनांक /Date.26.05.2020.

Chief Administrative Officer/Construction,  
Sr.DEN/Co-ord/SC, GTL, BZA, HYB, GNT, NED,  
Dy.CE/EWS/LGD & Dy.CE/LGDS

**Sub:** Addendum & Corrigendum Slip (ACS) NO.1 to SCR USSOR (Formation Works, Bridge Works and P.Way Works) -2019.

**Ref:** This office letter of even no. dt 26.02.2020.

\* \* \*

“Addendum & Corrigendum Slip (ACS) NO.1 to SCR USSOR (Formation Works, Bridge Works and P.Way Works) -2019” is enclosed herewith for information and necessary action please.

Signature valid

Digitally signed by SURYA  
VENKAT RAMA RAO  
JAGATS  
Date: 2020.05.26 16:44:03  
IST (J.S. Rama Rao)  
Reason: Approved

**Dy.Chief Engineer/Works**

**Copy to:** PCE, PFA/SC, SDGM/SC, CPD/SD, DRM/SC, BZA, GTL, HYB, GNT & NED  
CTE, CBE, CGE, CE/Wks, CE/TP, CE/P&D, CE/TM, CE/RSW, CE/BRH & CE/SD for kind  
information.

South Central Railway

Office of the Principal Chief Engineer

Addendum & Corrigendum Slip (ACS) NO.1 to  
SCR USSOR (Formation Works, Bridge Works and P.Way Works) -2019.

1. The following Notes i.e Note 3 and Note 4 are added in continuation of Note no.2 in the Description of the item no. 031120.

**“Note 3: The payment for this item shall be made for the clear inner cross section area of the parent RCC Box/Boxes and barrel length”.**

**“Note 4: The rate of this item includes excavation for main RCC Box within formation, thrust bed and approaches also”.**

2. The description of the item no 022040 shall be read as follows.

Item No	Description as existing	Description to be read as
024020	Providing and laying in position machine batched, machine mixed and machine vibrated Design Mix Cement Concrete of specified grade (cast in-situ) using 20mm graded crushed stone aggregate and coarse sand of approved quality in Drop and curtain wall and alike structures below bed level, including <b>centering, shuttering and</b> finishing complete as per drawings and technical specifications as directed by Engineer. Payment for cement, reinforcement and shuttering shall be made extra.	Providing and laying in position machine batched, machine mixed and machine vibrated Design Mix Cement Concrete of specified grade (cast in-situ) using 20mm graded crushed stone aggregate and coarse sand of approved quality in Drop and curtain wall and alike structures below bed level including finishing complete as per drawings and technical specifications as directed by Engineer. Payment for cement, reinforcement and shuttering shall be made extra.

3. A new Para 1.10 is included in "General and Operating Instructions" to SCR USSOR- 2019 as under.

**“The rates of items are inclusive of GST and other taxes, duties, levies or any other fees that may be payable under any Central Government, State Government or other Local Bodies Acts or Rules”.**

Signature valid

Digitally signed by ARUN KUMAR CHAUDHARY  
Date: 2020.05.26 12:46:39 IST  
Reason: Approved

(A. K. Chaudhary)  
CE/Works