

Name of the Project	:	VISUAL INSPECTION OF FOB AT ANAKAPALLE RAILWAY STATION
Location	:	ANAKAPALLE RAILWAY STATION
Location Co-ordinates	:	17°41'43.8"N 83°00'39.4"E
Date of Inspection	:	7th NOVEMBER, 2019



Summary:

- a) Cracks and Spalling observed at RCC slab panels of Span-1, 2, 3&7.
- b) Deflection observed in Girder (ISMB-400) of Span-5.
- c) Corrosion is observed in Bottom Chords of Spans 1, 2, 3, 4, 5, 6 & 7.
- d) Cracks are observed at RCC Slab Panels of Both Ramps.
- e) Corrosion is observed in Gusset Plates of Span-2
- f) Corrosion is observed in Girders & Floor Beams of Span-2.
- g) Spalling & Reinforcement exposure observed in Ramp slabs.

Tests to be conducted:

- a) Ultrasonic Thickness gauge to measures local thickness of a solid element.
- b) Elcometer (Coating thickness Gauge) to measures dry film thickness on steel surfaces.
- c) Ultrasonic Flaw detector to detect hidden cracks, voids, porosity, and other internal discontinuities in metals.
- d) Fillet weld gauge to measures the size of the weld.
- e) Profometer Test for concrete cover and diameter of rebar.
- f) Rebound Hammer test surface strength of concrete (For Pre-cast slab panels and staircase)


VISUAL INSPECTION OF STEEL FOOT OVER BRIDGE

Name of the Project	Visual inspection of FOB at Anakapalle railway station
Location	Anakapalle Railway Station
Date of Inspection	07-11-2019

PART 1 GENERAL INFORMATION AND OBSERVATION

1.1	Name of the Bridge	FOB/ CIRCULATING AREA TO CIRCULATING AREA	
1.2	Location Location co-ordinates	Anakapalle Railway Station 17°41'43.8"N 83°00'39.4"E	
1.3	Type of truss Structure	Vierendeel truss (fabricated with NG Rail) without diagonals	
1.4	Year of Construction	Not available	
1.5	Description of the main use of the bridge	Pedestrians Crossing	
1.6	Major Materials used in different parts of bridge	a. NG Rail b. Pre-cast RCC Slab panels (Floor slab, Staircase) c. RCC for Cast In-situ Slab	
1.7	Width of the Pathway (m)	2.5 m	
1.8	Length of the Pathway (m)	46 m	
1.9	No of Railway Lines Crossings	6 tracks Span 1 = No tracks Span 2 = 1 Span 3 = 1	Span 4 = 1 Span 5 = 2 Span 6 = 1 Span 7 = No tracks
1.10	Span arrangement (no x Span in meters)	1 x 4.8 m + 1 x 9.3 m + 1 x 4.6 m + 1 x 5 m + 1 x 10.2 m + 1 x 5 m + 1 x 4.6 m	
1.11	Vertical Clearance (from rail top to girder bottom)	5.941 m	
1.12	Head Room	No Roof Truss	
1.13	Damages due to accidental hitting, Grazing Marks	No Visible signs appear	
1.14	History of Repair/ Maintenance	Replacement of RCC Slab Panels in the spans 4,5&6 with RCC Slab & New Painting Observed	
1.15	Original Structural Drawings	Not available	

1.16 Key Plan



PART 2 IDENTIFICATION OF LOADS ON BRIDGE

		Yes/No	Notes
	Dead Loads at Roof level		
2.1	a) Pipeline - Utilities	No	
	b) Cables	Yes	a. Cables are protected with 1.5-inch HDPE pipe. (Refer fig :2) b. GI Pipes of Dia-60mm is observed c. No Roof Truss is provided.
	c) Roof Truss	No	
	d) Roof Sheet	No	
	e) load of advertising hoarding	No	
	f) load of train/coach display boards	No	No train coach display boards are provided
	g) Electrical equipment (OHE), signal	No	No electrical equipment and signal are provided
2.2	Dead Loads at Floor level		
	a) Additional wearing coat on Floor	No	No wearing coat observed (Refer fig :2)
	b) Provision of protective screen for passengers	Yes	Fence made of galvanized wire of 2 mm gauge and 2 mm galvanized sheet is used above OHE Line on both side of pathway is used for passengers Protection. (Refer fig :2)
	c) Type of Material used for mesh	GI wire mesh	


PART 3 STRUCTURAL SYSTEM OF THE BRIDGE

		Notes
3.1	Foundation details	Not visible at site
3.2	Pedestals	
	Trestles Connection Details	Not visible at site
	No. of Bolts and size	Not visible at site
	Thickness of Base Plate	Not visible at site
3.3	Roof Truss	
	Element of roof truss section	No Roof truss

	Size of roof truss		
	Connection of Roof elements		
3.4	Steel Truss		
	Type /Shape of Truss Section	Rail sections	a) Top Chord members are 60 x 120 x 120 (Head x Height x Base) Rail sections (Refer fig :4) b) There are 3 nos. of Bottom Chords Bottom Chord members are back to back connected 60 x 120 x 120 (Head x Height x Base) Rail sections (Refer fig :4) c) Addition 4 nos. of ISMB 400 Members are used as longitudinal girders in the spans 2&5. d) 60 x 120 x 120 (Head x Height x Base) Rail sections are used as vertical members. e) 45 x 90 x 90 (Head x Height x Base) Rail sections are used as Floor beams. f) 45 x 90 x 90 (Head x Height x Base) Rail sections are used as Bracings.
	Height of Girder/Truss (H)	1.10 m	
	Truss Support Condition	Rigid Connection	
	Type/Shape of Floor beam /Bracings	Rail Section	
	No of Floor beams/bracings	Span 1 = 4 No's Span 2 = 3 No's Span 3 = 7 No's Span 4 = 5 No's Span 5 = 5 No's Span 6 = 5 No's Span 7 = 5 No's	
	Arrangement of Bracings	Cross bracing	
	Type of Beam-Column Joint (shape of gusset plate if any)	Cleat Angle	
3.5	COLUMN		
	Type/Shape of Column section	Built up Section with Bull headed Rail	a. Stanchion Columns are 60 x 120 x 120 (Head x Height x Base) Rail sections. b. Cross Bracings in Stanchions are 75 x 75 x 8 mm Angles are used. (Refer fig :3)
	No of Columns/ support	3	
	Dimensions of Column		
	BEAM-Column joint (bolted, welded, riveted)	Bolted	
3.6	Floor of the Pathway		
	Material of Slab	Pre-cast slab panels for Spans 1,2,3 &7 Cast In-situ for Spans 4,5&6	Span 1,2,3&7 a. Pre-cast Reinforced concrete slab panels are used for floor slab of 100 mm thick. Span 4,5&6 a. Cast In-situ concrete slab is used for floor slab of 100 mm thick RCC slab.
	Thickness of Slab	100 mm	
	Condition of Slab from Bottom	Spalling observed is	
	Condition of Slab from Top	Spalling is observed	
3.7	Ramp Details		
	Number of Ramps	2 No's	Ramp is observed as Pre cast RCC Slab panels supported on 55 x 110 x 110 (Head x Height x Base) Bottom chords on both sides and middle of the ramp. (Refer fig :5)
	Number of Steps from Circulating Area – 1	-	
	Number of Steps from Circulating Area – 2	-	
	Material used for Ramp	Pre-cast RCC Slab Panel	

3.8	Ramp Railing		
	Type of Parapet Railing	Steel Railing	Ramps are provided with railing on both sides using 60 x 120 x 120 (Head x Height x Base) Angle sections and 65 x 65 x 8 mm Angles are used. (Refer fig :6)
	Height of Railing	1.1 m	

PART 4 SURVEY OF SIGNS OF DISTRESS, DEFORMATION IN BRIDGES	
4.1	✓ Exposed reinforcement is observed in span 1, 2, 3 and 7 th span and spalling is observed in ramp.
4.2	✓ Corrosion of gusset plate, bottom chord and Landing beam of Ramp




a) Corrosion of Gusset plate in 2nd Span of FOB



b) Corrosion of Gusset plate and bottom chord member in 3rd span of FOB



c) Corrosion of bottom chord member in 5th span of FOB



d) Corrosion of gusset plate connecting bottom bracings in 4th span of FOB



e) Corrosion observed in bottom rail



f) Corrosion observed in bottom rail



g) Corrosion of ramp landing beam

PART 4 SURVEY OF SIGNS OF DISTRESS, DEFORMATION IN BRIDGES			
	Defects	Location	Notes
	Cracking in Steel Members		No cracks are observed in Steel during visual inspection
	Cracking in RCC components	Slab panels	Cracks are observed in Pre-cast RCC slab panels of Ramps & Main Slab. (Refer: Part 4.1, Fig- b).
	Water seepage		No Seepage observed in the slab
	Spalling	Slab panels in ramp	Spalling is observed in ramp slab (Refer: Part 4.1, Fig- b).
	Rust straining	Bottom chord	Slight rusting is observed at all the joints of FOB at floor level (Refer: Part 4.2, Fig- c).
	Corrosion in Gusset plate	Span-2 nd , 4 th and 5 th	Corrosion is observed in gusset plate connecting bottom bracings (Refer: Part 4.2, Fig- a, b and d).
	Corrosion at steel-Concrete joint		No corrosion is observed at steel concrete joints along length of FOB



Fig 1: View of FOB and Ramps on both sides



Fig 2: FOB pathway, protective screen and cables on floor of pathway



Fig 3: Stanchion column details



Fig 4: Bottom view of FOB



Fig 5: Ramp details both ends of FOB



Fig 6: Damaged ramp railing



Fig 7: Inspection Team at Annakapalle FOB