दक्षिण मध्य रेलवे / **SOUTH CENTRAL RAILWAY**

Head Quarters Office ,
Work Branch, 5th Floor, Rail Nilayam,
SECUNDERABAD – 500071

No: W.CE/SD/KSN/Insp/2024/35

Dt: 09.01.2026

SrDEN/Co/SC,BZA,GTL,GNT,HYB,NED,
CPM/GS-I/SC, GS-II/SC,GTL,GNT.

Sub: Providing thicker Tactile flooring at stations with Parcel Handling Operations –reg.

During a Preventive Check by Vigilance department, it was observed that 9.80mm thick Tactile flooring Tiles are being laid at some Amrit Stations. Vigilance opined that the thickness of tactiles being provided is less compared to adjacent flooring thickness and therefore is not uniform thereby making it prone for breakage, especially where parcel loading and unloading operations are carried out.

As such, it is advised to provide approved Tactile tiles of thickness matching with the surrounding granite slab/chequered tile flooring for uniformity so as to withstand higher impact loading without breaking (minimum 30mm thick) by adopting suitable NS item, at locations where parcel loading and unloading operations are carried out.

This issues with the approval of PCE.

(AVH Mallikarjuna)
Chief Engineer/Station Development.

Copy to SDGM for kind info. This is w.r.t Lr.No.G.265/PC/E/20250400634, dt:07.07.25 pl.
Copy to CAO/C,CAO/C/RSP for kind information pl.
Copy to CE/P&D,CGE,CE/C/Plg, CCM/PS for kind information pl.